

ALU-ALU RAW MATERIAL COST REPORT

EXECUTIVE SUMMARY - REVISION 10

SELLING PRICE	FINAL RM COST	BASE COST (M2)	IDEAL COST (KG)	STD WASTAGE	GROSS MARGIN
Rs 490.00	Rs 395.90	Rs 94.12	Rs 373.49	Rs 22.41	19.20%
Rs/kg	Rs/kg Consumed	0.25199 kg Yield	100% Efficiency	+6.00% Loss	Rs 94.10/kg

1. MATERIAL CONTRIBUTION & COST BREAKDOWN				
MATERIAL SPECIFICATION	GSM	RATE (RS)	COST (RS/M2)	COST (RS/KG)
OPA 25 um (1.15 g/cm3)	28.75 (11.41%)	240.00	6.90	27.38 (7.33%)
Aluminium foil 8021 50 um (2.71 g/cm3)	135.50 (53.77%)	520.00	70.46	279.61 (74.87%)
PVC 60 um (1.35 g/cm3)	81.00 (32.14%)	170.00	13.77	54.65 (14.63%)
Adhesive Calculated via 50kg mix/Tonne	6.74 (2.67%)	-	2.99	11.85 (3.17%)
Total Output Yield & Base Cost	251.99 (100.00%)		Rs 94.12	Rs 373.49 (100.00%)

2. ADHESIVE FORMULATION (100:15:100)	
Mixing Ratio:	100:15:100 equates to a total batch size of 215 kg of wet mixture.
Consumption Metric:	Exactly 50 kg of wet mixture produces 1 Tonne (1,000 kg) of finished output.
Equivalent Impact:	Dry GSM applied to the foil structure is ~6.74 GSM.

COMPONENT	MIX (KG)	RATE (RS/KG)	TOTAL COST (RS)
KUB130	100	351	35,100
Hardener (Neo Force)	15	350	5,250
Ethyl acetate	100	106	10,600
Batch Total (Wet Mixture)	215	236.98 (Avg)	50,950